

Addendum #1
To
Kindergarten Roof Replacements
Rochester School District
11/24/2020

The following is addendum is being issued for clarification.

Chamberlain:

- Include ¼” Tapered Cricket between drains

E. Rochester:

- Exclude radius overhang roof on front of building from scope
- Remove reference of “Air and Vapor Barrier” from insulation step; *Furnish and install (1) layer of new 1.5” Insulbase 20 psi Insulation loose laid over **air and vapor barrier**.*

Gonic:

- Include additional PVC roof area in front of building, scope to mirror that of the initial PVC roof area plus the addition of walk mats.
- Remove reference of “Air and Vapor Barrier” from insulation step; *Furnish and install (1) layer of new 1.5” Insulbase 20 psi Insulation loose laid over **air and vapor barrier**.*

All Schools:

Dumpsters will be provided at each work location at the expense of the Rochester School District and should not be included in the bid.

Any questions or concerns can be addressed to:

David G. Totty
Director of Facilities
Rochester School District
(603) 332-3678 ext. 1145